

SHOPPA'S
MATERIAL HANDLING

Ai ADVANCED
INTRALOGISTICS

UPRIGHT

REPLACE
VS.
REPAIR

REPLACE

VS.

REPAIR

Unload 20 pallets and stage out of the way	45 mins
Install crew must utilize equipment to disassemble upright and wire decks	45 mins
Anchors cut, install new uprights, beams & wire deck, then anchor.	45 mins
Reload all pallets	45 mins
Materials Shipment	2-3 Days

LEAD TIME: 3+ DAYS

Cost Breakdown

NEW 42" x 240" Upright	\$265
(2) 1/2" Anchors	\$4
Local Delivery	\$250
Labor	\$575
Equipment Rental & Delivery	\$990

COST: \$2,084

Unload 2-8 pallets and stage out of the way <small>(*total load must not exceed 10,000 lbs)</small>	20 mins
Install crew raise the upright and cut out damage	15 mins
Anchors cut, install repair kit, then anchor.	30 mins
Reload all pallets	20 mins
Materials Shipment	1 Day

LEAD TIME: 1 DAY

Cost Breakdown

24" Repair Kit	\$575
(4) 3/4" Anchors	Included
Local Delivery	\$75
Labor	\$250
Equipment Rental & Delivery	No need!

COST: \$900

This comparison is based on standard in-stock repair kit for damaged 20' tall upright with 4 beams levels and wire deck.

TOTAL COST SAVINGS: \$1,184+

REPAIR KIT BENEFITS

- Lead time savings up to **48+ hours**
- Install time savings up to **1.5+ hours**
- Anchors installed in between front and back column eliminate any problems that may occur with existing upright footplate anchor hole or damaged concrete.

Contact Us

866.506.2200

shoppasmaterialhandling.com

800.992.1431

advancedintralogistics.com